

WELCOME



Modern Landfill & Archaea Energy Tour

May 25, 2023



WHO WE ARE

- Family owned & operated
- Fully integrated solid waste management company based out of Lewiston, NY
 - Collections, transfer station, MRF, portable toilets, landfill
- Started in 1964 with two trucks
- Now over 700 employees and 350 trucks
Operations in WNY and in southern Ontario, Canada

MODERN LANDFILL

- Opened in 1983
- Permitted site life through late 2030's
- 232 acres permitted
- ~169 double composite lined acres constructed
 - Includes 44 acres double composite overfill liner
 - MSE berm
 - ~2,700 LF hydraulic barrier wall constructed in 2022
 - 7.4 acre cell to be constructed in 2023
- ~10 acres capped

MODERN LANDFILL

- Open six days per week (closed on Sundays)
- Accept MSW, non-hazardous industrial wastes, asbestos, C&D debris, contaminated soil, and sludge wastes
- Solidification pits
- MRF
- Residential drop-off




MODERN LANDFILL



CONSTRUCTION - 2021


- Section IV Area 2B2 – approx. 6.2 ac cell
- Approx. 250 LF of MSE berm



BASELINER CONSTRUCTION

- Prepared subgrade
- Porewater collection system
- 24-inch compacted secondary soil liner (clay)
- 80-mil textured HDPE geomembrane
- Secondary leachate collection system
- 12-inch structural fill layer
- Geosynthetic Clay Liner (GCL)
- 80-mil textured HDPE geomembrane
- 16 oz/sy NW cushion geotextile
- Primary drainage layer
 - Stone, TDA

PLACE GCL WITH THE LONGITUDINAL DIMENSION PARALELL TO THE NORMAL TOE OF SLOPE FOR THE PRIMARY GEOMEMBRANE LINER, PROVIDING A MINIMUM FIVE FOOT RUN UP THE 3H:1V SLOPE




DAIGLER ENGINEERING P.C.
engineering · science · design
 1711 GRAND ISLAND BLVD. GRAND ISLAND, NEW YORK 14072

MODERN LANDFILL, INC.		TYPICAL BASELINER DETAIL			FIGURE 6-3
SCALE: NOT TO SCALE	REVISION # 0	PROPOSED LANDFILL FOOTPRINT MODIFICATIONS			
August 2008	TOWN OF LEWISTON	NIAGARA COUNTY	NEW YORK		



POREWATER SYSTEM

- Excavation of trenches
- Installation of porewater geocomposite
- Installation of PVC pipe
- Separator GT



SECONDARY SOIL LINER

- Installed in 3 lifts
- Each lift tested:
 - Max. permeability 1×10^{-7} cm/s
 - Min. 90% max. dry density



SECONDARY SOIL LINER




SECONDARY GEOMEMBRANE

- Smooth surface
- Max. particle size of 1 inch



SECONDARY LEACHATE COLLECTION

- Installation of geocomposite (manually)
- Placement of structural fill
- Installation of PVC pipe



GCL

- Powdered bentonite along seams
- Max. permeability 5×10^{-9} cm/s
- Needle inspection



PRIMARY GEOMEMBRANE

- Fusion and extrusion welding
- Testing and repairs



GEOTEXTILE, STONE, TDA



MSE BERM CONSTRUCTION



MSE BERM CONSTRUCTION




CONSTRUCTION – 2022

- 2,687 LF of Hydraulic Barrier Wall (HBW)
- \$1+ million project
 - Water
 - Surveying
 - Working platform
 - Spoils removal, site restoration
 - Stormwater, E&S, dust controls



WHY HBW?


- Glaciolacustrine sand and silt layer is transmissive
- With shallow GW table, dewatering efforts may be ineffective in future cells




HYDRAULIC BARRIER WALL

- Installed by DeWind using One-Pass Trenching System
- Blended in-situ soils with added source water, cement, and bentonite (as needed)
- Max. permeability of 1×10^{-6} cm/s and compressive strength of 20 psi (at 28 days)
- Approx. 2 ft wide and keyed at least 2 ft into underlying dense till
- Average 1 ft per minute

HYDRAULIC BARRIER WALL



HYDRAULIC BARRIER WALL



QUESTIONS?

